

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE NW SE

SEC. 20 TWP. 11 RGE. 18 *W*

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Wasinger

Operator C & G Drg Co Address Wichita, Kans

Field _____ County Ellis

Total Depth 3637 Feet.

Plugging Contractor Sun Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 210' circulated with cement - 5 1/2" at 3619' with

100 sax cement behind - Squeezed at 386' with 150 sax cement -

perforated at 724' and squeezed with 150 sax cement - cement

circulated to 0'.

Pumped hole full commercial mud (30 sax gel) pumped cementing

plug to 260' followed by 30 sax cement - cement 200' to 0'.

No pipe recovery - cementing by Sun Cementing Co - 400# pump pressure.

John Petty
District Conservation Agent

Date 7-10-55

STATE OF KANSAS
7-16-55

PLUGGING
FILE SEC 20 T 11 R 18 W
BOOK PAGE 135 LINE 2