

## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

FILE NO. 89-31LOCATION NW SE SWSEC. 20 TWP. 11 RGE. 18Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 5 Lease \_\_\_\_\_ Hand \_\_\_\_\_Operator Phillips Pet Co Address Box 779 Great Bend, KansField \_\_\_\_\_ County EllisTotal Depth 3676 Feet.Plugging Contractor West Supply CoPlugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

9 5/8" at 1191' circulated with 425 sax cement - 7" at 3337'  
with 150 sax cement behind - Plugs to 3355', perforated at 3350',  
Filled with sand to 3320', set 5 sax cement with dump bailer,  
pulled 2450' 7" - filled with mud to 275', set plug and 30 sax  
cement - mud to 35', set rock bridge and filled to bottom cellar  
with cement.

Cementing by Halliburton Cementing Co.

**PLUGGING**

FILE SEC 20 TWP 11 R 18W  
 BOOK PAGE 89 LINE 31

1-18-55

Ellen P. [Signature]  
 District Conservation Agent  
 Date 1-15-55