

15-051-20415-0000

Form CP-3
Rev. 6-26-62

JP

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sage Drilling Co., Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas

Lease Name ~~Meaden~~ Frisbie Well No. 1

Location NE NE NW Sec. 20 Twp. 11 Rge. (E) (W)18

County Ellis Total Depth 3567'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 1P Day 17 Month 4 Year 1969

The Above well was plugged as follows:

RTD 3567' 8 5/8 csg set at 249' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: *Geo J. Murray*
Well Plugging Supervisor

INVOICED
DATE 4/21/69
INV. NO. 9642-4