

K
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Pet Co

Complete Address: Box 287 Great Bend, Kansas

Lease Name Ancobs Well No. 4

Location NE SW NE ^{SE} ^{JR} ^{KCC} Sec. 26 Twp. 11 Rge. (E) (W) 18

County Ellis Total Depth 3566

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 3PM Day 9 Month 8 Year 63

The Above well was plugged as follows:

8 5/8" 1314' circulated with cement - 5 1/2" 3564' with 200 sax cement.
Sanded back to 3550', set 5 sax cement with dump bailer p 5 1/2" into
at 665' - pulled 665' 5 1/2" - filled hole with heavy gel mud to 550',
set 20 sax cement at 550', heavy gel mud to 200', set 20 sax cement
at 200', heavy gel mud to 35', cement 35' to bottom cellar -
(used total of 17 sax Gel Mud)

Mudding and cementing by Knight Company Pump .

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/13/63

INV. NO. 7579-W

Signed: *[Signature]*
Well Plugging Supervisor