

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Phillips Petroleum Company

Complete Address: Box 287 Great Bend, Kansas 67530

Lease Name Ancobs Well No. 1

Location NE NE NE Sec. 26 Twp. 11 Rge. 18 (E) (W) X

County Ellis Total Depth 3645

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2 P Day 9 Month 3 Year 1968

The Above well was plugged as follows:

Total Depth 3645' 8 5/8 csg set at 1403' cwc.

5 1/2' csg set at 3640' cw 200 sc cement.

Filled with sand to 3600' and dumped 5 sc cement with dump bailer.

Recov. 2445' of 5 1/2' csg.

Mud to 500' set 10' rock bridge and 25 sc cement plug.

Mud to 50' set 10' rock bridge and filled to surface with 15 sc cement.

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/13/68
INV. NO. 7414-W