

KANSAS
STATE CORPORATION COMMISSION 7-12-61

RECEIVED
ST. CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis
Location: SW NE NE Sec. 26 Twp. 11 Rge. 18 (E) (W)
Name of Field: _____ Total Depth: 3622

I have this date completed supervision of plugging of:

Lease Name: Ancobs Well No. 2
Operator's Full Name: Phillips Pet Co
Complete Address: Box 779 Great Bend, Kansas
Plugging Contractor: Knight Casing Pulling
Address: Chase, Kansas License No. 436
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____
Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No
If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 4 Month 4 Year 61

The above well was plugged as follows:

8 5/8" 1294' circulated with cement - 5 1/2" 3622' with 200 sax cement.
perforated 3555'.
Filled with sand to 3540', set 4 sax cement with dump bailer, pulled
2573' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500',
displaced 20 sax cement through 5 1/2" at 500', heavy mud to 180', displaced
20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10
sax cement to bottom cellar.
Mudding and cementing by Knight Pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 4/28/61
INV. NO. 3003-W