

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ellis County, Sec. 31 Twp. 11S Rge. 18W (E) (W)
Location as "NE/CNW&SW4" or footage from lines. S 1/2 SE SE

Lease Operator Hummon Oil Co.

Lease Name Pfeifer Well No. 2

Office Address 6409 E. 14th, Wichita, Ks. 67206

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed April 3 1970

Application for plugging filed 19

Application for plugging approved July 13 1972


Plugging commenced Sept. 16 1972

Plugging completed Sept. 16 1972

Reason for abandonment of well or producing formation
Not required for production

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation salt water disposal Depth to top 3671 Bottom 3676 Total Depth of Well 3676 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	248	none
				5 1/2	3671.5	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

50 sacks cement - 3676 to 3276. 25 sacks gel & 3 sacks hulls 3276 to 680.
85 sacks cement 680 to 6'.

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co.
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. E. Leith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Leith

6409 E. 14th, Wichita, Kansas 67206
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of October 1972.

Schaula L. Harrington
Notary Public.

My commission expires May 1, 1974

COMPANY HUMMON OIL, INC.

SEC. 31 T. 11S R. 18W
LOC. C S/2 SE SE


FARM Pfeifer NO. 2

TOTAL DEPTH 3,676'
COMM. February 27, 1970
SHOT OR TREATED
CONTRACTOR H-30, Inc.
ISSUED

COMP. March 9, 1970

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1972
CONSERVATION DIVISION
Wichita, Kansas

Ellis
KANSAS



CASING

20 10
15 8 5/8" 248' cemented w/160 sx cement ELEVATION 2095 KB
12 6
13 5 1/2" 3671.5' cemented w/200 sx cement
DV Tool set @ 1410' cemented w/400 sx cement
FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock & Shale 248
Shale & Shells 650
Shale 875
Sand 1080
Red Bed & Shale 1430
Anhydrite 1448
Shale & Salt 1960
Shale & Lime 2250
Lime & Shale 2430
Lime & Shale Streaks 2650
Lime & Shale 3240
Lime 3272
Lime & Shale 3296
Lime 3378
Lime & Shale 3505
Lime 3576
Lime & Shale 3655
Lime 3676
Rotary Total Depth 3676

ELECTRIC LOG TOPS:

Topeka 3098-1003
Heebner Shale 3324-1229
Toronto 3346-1251
Lansing 3368-1273
Base K.C. 3602-1507
Arbuckle 3656-1561
Log T.D. 3676-1581
Rotary T.D. 3676-1581

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
Arlo B. Romer

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for Sedgwick county and state this 12th day of March, 1970.

Martha Hartpence
Martha Hartpence-Notary Public

My Commission Expires: April 21, 1971

