

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ellis County. Sec. 20 Twp. 11 Rge. 18 (E) (W)

Location as "NE/CNW&SW" or footage from lines. NE 1/2

Lease Owner Morgenstern & Specter

Lease Name Wassinger "A" Well No. \_\_\_\_\_

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 3-23-64 \_\_\_\_\_ 19\_\_

Application for plugging filed Oct. 30, 1964 \_\_\_\_\_ 19\_\_

Application for plugging approved Oct. 31, 1964 \_\_\_\_\_ 19\_\_


Plugging commenced October. 23, 1964 \_\_\_\_\_ 19\_\_

Plugging completed October. 28, 1964 \_\_\_\_\_ 19\_\_

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas

Producing formation Arbuckle Depth to top 3616 Bottom 3618 Total Depth of Well 3621 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	172 ft.	none
				5 1/2" OD	3618 ft.	2990

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged, back with sand to 3600-feet, dumped 5- sacks cement.  
Circulated mud at 600-feet, pumped 20-sacks cement at 550-feet.  
Pumped 20- sacks cement at 250-feet.  
Set a rock bridge at 35-feet, put ten sacks cement on top.

STATE CORPORATION COMMISSION

NOV 12 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor LYNCH CASING PULLING COMPANY. NO. 457

Address R.Rt. 4 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

Morgenstern & Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10<sup>th</sup> day of November, 1964

My commission expires Feb 29, 1968

Barbara King Notary Public.

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-051-19452-0000

Company- JAMES W. HERSHBERGER  
Farm- Wasinger "A" No. 1

SEC. 20 T. 11 R. 18W  
175' S/SE SW NE

Total Depth. 3621'  
Comm. 3-12-64 Comp. 3-23-64  
Shot or Treated.  
Contractor. Terrel Drilling & Producing  
Issued. 6-27-64

County Ellis  
KANSAS



Elevation. 2069' DE

Production. 25 BOFD, NW

CASING:

8" 172' cem w/140 sx.  
5" 3618' cem w/100 sx.

Figures Indicate Bottom of Formations.

white rock	70
shale	635
sand & shale	1059
shale & redbed	1368
Anhydrite	1406
shale	1470
lime	2420
shale & lime	2705
lime & shale	2960
shale	3046
lime & shale	3100
lime	3164
lime & shale	3180
lime	3276
lime & shale	3320
Kansas City Lime	3354
lime	3400
Kansas City Lime	3484
lime	3565
lime & shale	3620 RTD
lime & shale ?	3621
Total Depth	
TOPS: LOG	
Topeka	3046
Heebner	3271
Toronto	3280
Lansing	3312
Base Kansas City	3541
Cherty Conglomerate	3573
Simpson Shale	3586
Simpson Dolomite	3602
Arbuckle	3616

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas