

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-20289-0000

API NUMBER n/a

LEASE NAME Wasinger

WELL NUMBER #1

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 20 TWP. 11S RGE. 18 (E) or (W)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 100 N. Main, Suite 500, Wichita, Kansas 67202-1308 COUNTY Ellis

PHONE# (316) 262-3573 OPERATORS LICENSE NO. 5004

Date Well Completed 8-16-68

Character of Well Oil

Plugging Commenced 5-9-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-9-91

The plugging proposal was approved on 5-9-91 (date)

by Herbert Deines (KCC District Agent's Name).

Is ACO-1 filed? n/a If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 3604 Bottom Open Hole T.D. 3611

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	240 ft.	none
				5 1/2	3606 ft.	none

AUG 14 1991

CORPORATION DIVISION
KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated with 3 SPF at 550 feet and 1370 feet. Ran tubing to 2200 feet and spotted 85 sx of 60/40 Pozmix with 8% gel. Pulled tubing to 1100 feet and circulated cement to surface with additional 85 sx of 60/40 Pozmix with 8% gels. Put in 5 1/2" swage and pumped 35 sx of 60/40 Pozmix with 8% gels and 50% of hulls. Max. pressure of 500 psi, ISIP 400%. Tied on to annulus

(If additional description is necessary, use BACK of this form.)
and pressured to 300 psi, would not take cement. Finished job at 3:30 p.m. on 5-9-91.

Name of Plugging Contractor BJ Services License No. _____

Address P.O. Box 69 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Richard A. Hiebsch

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch
Richard A. Hiebsch, Vice President

(Address) Vincent Oil Corporation
100 N. Main, Suite 500 Wichita, KS

13th day of August, 1991

Julie K. Stout
Julie K. Stout Notary Public



AND SWORN TO before me this _____ day of _____, 1991
Commission Expires: July 23, 1993