

API NUMBER 15-051-249750000

LEASE NAME Wasinger

WELL NUMBER 4

1,320 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 20 TWP. 11 RGE. 18 (E) or (W)

COUNTY Ellis

Date Well Completed 8-26-97

Plugging Commenced 8-26-97

Plugging Completed 8-27-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Castle Resources, Inc.

ADDRESS Box 87, Schoenchen, KS. 67667

PHONE/(913) 625-1555 OPERATORS LICENSE NO. 9860

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-26-97 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No if not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3,620'

Show depth and thickness of all water, oil and gas formations.

9-9-97

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	210'	Cmtd. w/135 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set:
Push bridge plug to 1,360', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 750', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 250', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor
(Employee of ~~Operator~~ or ~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 97

Leath Phillips
Notary Public

My Commission Expires: _____





Shields


WELL LOG

Russell, Kansas

ORIGINAL

Operator: Castle Resources, Inc.
 Well: Wasinger #4
 Commenced: August 19, 1997
 Completed: August 27, 1997
 Contractor: Shields Drilling Co.

Well Description: W/2 E/2 SE/4
 Sec. 20-11S-18W
 Ellis Co., KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	210'	Cmtd. w/135 sax

Elevation: 2,045' KB

Treatment:

Production: D & A

Tops:

15-051-24975-0000

..... Figures Indicate Bottom of Formations

Rock & Shale	210'	
Shale	310'	
Shale & Sand	1,343'	
Anhydrite	1,379'	
Shale & Sand	1,503'	
Shale &	2,860'	
Shale & Lime	3,055'	
Lime	3,203'	
Lime & Shale	3,404'	
Lime	3,620'	RTD

Notes