


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 20 Twp. 11S Rge. (E) 18(W)
Location as "NE/CNWxSWx" or footage from lines NE NE NW
Lease Owner Sage Drilling Co., Inc.
Lease Name Frisbie Well No. 1
Office Address 500 Bitting Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 17, 1969
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced April 17, 1969
Plugging completed April 17, 1969
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Leo Massey of Hays)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3567 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	248'	8-5/8"	4/10/69	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 600 Feet; Plug and 70 sax Cement;
Mud to 240 Feet; Plug and 20 sax Cement;
Mud to 40 Feet; Plug and 10 sax Cement
to Base of Cellar. Job completed @ 1 P.M.
on 4/17/69.


RECEIVED
STATE CORPORATION COMMISSION
APR 23 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Globe Cementing Co.
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 69
November 26, 1970.
Louise K. Whitted - Notary Public.



DRILLERS LOGFRISBIE NO. 1

CASING RECORD:	OPERATOR: Sage Drilling Co.	DESCRIPTION:
8-5/8" Surface @ 248' w/200 sax cement	CONTRACTOR: Sage Drilling Co.	NE NE NW Sec. 20-11S-18W Ellis Co., Kansas
TOTAL DEPTH: 3567'	COMMENCED: April 9, 1969	ELEVATION: 1917KB
	COMPLETED: April 17, 1969	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Rock	0	40	
Shale & Shells	40	519	
Sand	519	575	
Shale	575	706	
Sand	706	889	
Shale & Shells	889	1209	
Anhydrite	1209	1250	
Shale & Red Bed	1250	1595	
Sand & Shale	1595	1658	
Shale & Shells	1658	1855	
Shale & Lime	1855	1965	
Lime & Shale	1965	2205	
Shale & Lime	2205	2585	
Lime & Shale	2585	2721	
Shale & Shells	2721	2893	
Shale & Lime	2893	2935	
Lime w/Shale Streaks	2935	3030	
Lime & Shale	3030	3071	
Lime	3071	3455	
Lime & Shale	3455	3487	
Lime	3487	3567	D&A

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 21st day of April, 1969.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.