

WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION


Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Ellis County. Sec 26 Twp 11S Rge. 18 (E) (W) Location as "NE1/4NW1/4SW1/4" or footage from lines NE1/4 NE1/4 SW1/4 Lease Owner Bay Petroleum Corporation Lease Name Jacobs Well No. 1 Office Address P. O. Box 957, Denver, Colorado Character of Well (completed as Oil, Gas or Dry Hole) Dry hole Date well completed December 9, 1947 Application for plugging filed December 9, 1947 Application for plugging approved December 9, 1947 Plugging commenced December 9, 1947 Plugging completed December 9, 1947 Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Strough Producing formation Depth to top Bottom Total Depth of Well 3715 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Formation, Content, From 0, To 1389', Size 8 5/8", Put In 1389', Pulled Out.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- From 3715 feet to 1380 feet - Heavy Rotary mud
" 1380 " to 1379 " - Wooden Plug
" 1379 " to 1329 " - 15 Sacks Cement by Sun Cementing Co.
" 1329 " to 600 " - Heavy Rotary Mud
" 600 " to 599 " - Wooden Plug
" 599 " to 549 " - 15 Sacks Cement by Sun Cementing Co.
" 549 " to 30 " - Heavy Rotary Mud
" 30 " to 29 " - Wooden Plug
" 29 " to 6 " - 10 Sacks Cement by Sun Cementing Co.
" 6 " to Surface - Cellar

12-19-47

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Bay Petroleum Corporation Address P. O. Box 957, Denver, Colorado

STATE OF Kansas COUNTY OF Barton

Glenn Peel Drilling Co., Inc. (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Glenn Peel Drilling Co., Inc.

(Signature) J. B. Anderson

P. O. Box 359, Hoisington, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 15th day of December, 1947

My commission expires June 4, 1951 Notary Public.

PLUGGING FILE # 26 11 18W 4 14

DRILLER'S LOG

Company: The Bay Petroleum Corporation

Sec. 26 Twp. 11S Rge. 18W  
NE NE SW

Farm: Jacobs Well No. 1

Total Depth: 3715'

Comm.: 11-22-47; Comp.: 12-9-47;

County: Ellis  
Kansas

Contractor: Glenn Peel Drilling Co., Inc.

Casing:

Elevation:

8 5/8" 1389' Cen.

Production: Dry

Figures below indicate bottom of formations

Surface clay	40
Shale and sand	265
Shale and shells	430
Sand & shale w/iron strks	800
Shale & shells	875
Sand	1050
Shale & shells	1375
Anhydrite	1425
Shale and shells	1955
Shale and Lime	2090
Lime w/shale streaks	2240
Lime & shale	2665
Lime	2710
Lime & shale	3100
Lime w/shale streaks	3170
Lime	3665
Arbuckle Lime	3715
Total Depth	3715

The above information is, to the best of our knowledge, true and correct.

GLENN PEEL DRILLING CO., INC.

BY: *Glenn Peel*

Subscribed and sworn to before me this 15th day of December, 1947.

*Marian M. Herbert*  
Notary Public