


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Ellis County. Sec. 26 Twp. 11 Rge. (E) 18 (W)
Location as "NE/CNW&SW&" or footage from lines 990' ENL and 990' EEL. NE/4
Lease Owner Phillips Petroleum Company
Lease Name Ancobs Well No. 2
Office Address Box 779 - Great Bend, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed October 17, 19 47
Application for plugging filed March 7, 19 61
Application for plugging approved March 9, 19 61
Plugging commenced March 29, 19 61
Plugging completed April 4, 19 61
Reason for abandonment of well or producing formation Unconconomical to operate

If a producing well is abandoned, date of last production February 15, 19 61
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3555 Bottom Total Depth of Well 3622 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Anhydrite	Dry	1255		8 5/8"	1294'	None
Heebner	Dry	3205		5 1/2"	3675'	2559'
LKC	Dry	3224				
Conglomerate	Dry	3501				
Simpson Shale	Dry	3525				
Simpson Dolomite	Dry	3536				
Simpson Sand	Dry	3553				
Arbuckle	Oil	3555				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand from 3633' to 3494'. Dumped 4 sx. cement from 3494' to 3462'.
Mudded hole from 3462' to 500'. Dumped 20 sx. cement to 440'. Mudded to
180'. Dumped 20 sx. cement to 120'. Mudded to 40'. Set rock bridge to
30'. Dumped 10 sx. cement in filling to base of cellar.

4-6-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.
Address Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, ss.
M. E. Michael (employee of owner) or ~~conservation division~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *M. E. Michael*
Box 779 - (Gt. Bend, Kansas,
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 61

My commission expires 11/18/61

Notary Public.



26-11-18W
15-051-05221-0000

EXPLORATION RECORD

Lease Ancobs

Well 2

Formation Name	Top	Base	Remarks
Clay Shale and Shells	0	70	Elevation: 1993' DF
Shale and Shells	70	540	
Sand	540	633	
Pyrite and Rock	633	664	
Pyrite and Sand	664	695	
Shale	695	710	
Shale and Shells	710	1140	
Red Bed	1140	1210	
Shale	1210	1217	
Sandy Red Bed	1217	1240	
Gyp	1240	1255	Top Anhydrite - 1255
Anhydrite	1255	1290	
Red Bed and Shale	1290	1305	
Shale and Shells	1305	2020	
Broken Lime	2020	2170	
Lime	2170	2360	
Lime and Shale	2360	2425	
Broken Lime	2425	2585	
Lime	2585	2730	
Shale and Shells	2730	3035	
Lime and Shale	3035	3100	
Broken Lime	3100	3140	Top Heebner 3205
Lime and Shale	3140	3501	Top LKC 3224 Cong. 3501
Conglomerate	3501	3519	
Shale	3519	3555	Top Simpson Shale 3525, Dolomite 3536, Sand 3553
Lime	3555	3660	Arbuckle 3555

RECEIVED
STATE CORPORATION COMMISSION
APR 3 1961
CONSERVATION DIVISION
Wichita, Kansas