

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Ellis County, Sec. 26 Twp. 11S Rge. 18 (W)

Location as "NE/CNW/SE" or footage from lines 1650 fr. E & 660' fr. North, NE/4

Lease Owner Phillips Petroleum Company

Lease Name Ancoba Well No. 5

Office Address Box 779, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 27 19 55

Application for plugging filed November 28 19 55

Application for plugging approved November 29 19 55

Plugging commenced November 28 19 55

Plugging completed November 28 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Patty

Producing formation Arbuckle Depth to top 3591 Bottom 3600 Total Depth of Well 3600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	3233	3253	9-5/8"	334.73 OA	Nona
Toronto	Dry	3253	3276			
Lansing-Kansas City	Dry	3276	3517			
Simpson Shale	Dry	3561	3591			
Arbuckle	Dry	3591	3600			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole 3600' to 300'. Pushed 9-5/8" Halliburton Plug to 300'. Dumped 20 sx. cement in filling to 260'. Filled with mud to 40'. Pushed Halliburton 9-5/8" plug to 40'. Dumped 1/2 sack hulls and 10 sx. cement in filling to base of cellar. Well plugged and abandoned 5:00 P.M. 11-28-55.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & R Drilling Company

Address Russell, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

A. J. Willis (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


Box 779, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 55

My commission expires November 18, 1957

Notary Public.



EXPLORATION RECORD

PHILLIPS PETROLEUM COMPANY - Ancobs #5 - 1650' from East and 660' from North Lines,
NE/4 Section 26-11S-18W, Ellis County, Kansas.
Dry Hole

Lease Ancobs

Well 5

Formation Name	Top	Base	Remarks
Rock and hard blue shale	0	120	
Gravel	120	150	
Shale	150	220	
Blue Shale	220	395	
Blue Shale and red rock	395	520	
Shale and lime and shells	520	700	
Iron Pyrite and shale	700	730	
Shale and shells	730	1060	
Shale and redbed	1060	1280	
Anhydrite	1280	1320	
Shale and shells	1320	1525	
Shale	1525	1560	
Shale and lime streaks	1560	2050	
Lime and shale	2050	2770	
Light gray shale	2770	2820	
Lime and shale	2820	3235	
Lime	3235	*3600	**Drill Stem Test
<u>FORMATION TOPS</u>			
Heebner	3233		
Toronto	3253		
Lansing-Kansas City	3276		
Base Kansas City	3517		
Simpson Shale	3561		
Arbuckle	3591		
Rotary Total Depth	3600		
			*Not penetrated at 3600' TD **See Daily Report Detailed

PLUGGING
 FILE SEC 26 T 11 R 19 W
 BOOK PAGE 20 LINE 6