15-051-00987-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ellis County. Sec. 26 Twp. 11 Rge. 18 (E) XX (W)

Location as "NE/CNW¼SW¼" or footage from lines SW SW SE

Lease Owner Anschutz Drilling Company, Inc.

Lease Name Jacobs Well No. 1

Office Address 709 Union Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-16 19 50

Application for plugging filed via telephone 3-16 19 50

Application for plugging approved via telephone 3-16 19 50

Plugging commenced 3-16 19 50

Plugging completed 3-16 19 50

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production ..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation ..... Depth to top ..... Bottom ..... Total Depth of Well 3640 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	186'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ..... feet to ..... feet for each plug set.

Filled hole with heavy mud, set bottom plug at 180', put 15 sacks cement through drill pipe on bottom plug, filled with heavy mud to 40', set top plug at 40' filled with cement to bottom of cellar

03-21-50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anschutz Drilling Company, Inc.

Address 709 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

H. R. Jensen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Jensen

709 Union National Bank Bldg., Wichita, Ks
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of March 19 50

Marcha Kenyon
Notary Public.

My commission expires Sept 12, 1953

22-7377-s 4-49—10M

PLUGGING
FILE SEC 26 T 11 R 18
BOOK PAGE 143 LINE 22

15-051-00987-0000

ANSCHUTZ DRILLING COMPANY, INC.

Jacobs #1, SW SW SE 26-11-18
Ellis County, Kans.

COMMENCED: 3-4-50
COMPLETED: 3-16-50

0	30	Gravel & clay
30	130	Shale and shells
130	160	Shale and shells
160	187	Lime shells and shale
187	275	Shale and shells
275	380	Shale and shells
380	550	Gray shale
550	735	Sand and shale
735	795	Shale and shells
795	940	Sand and pyrite
940	1080	Shale and shells
1080	1290	Shale and shells
1290	1310	Anhydrite
1310	1480	Shale and shells
1480	1690	Shale and shells
1690	1795	Salt shale and shells
1795	1870	Shale and shells
1870	1985	Lime and shale
1985	2110	Lime and shale
2110	2215	Lime and shale
2215	2320	Lime and shale
2320	2400	Lime and shale
2400	2510	Lime and shale
2510	2635	Shale and lime
2635	2720	Lime and shale
2720	2815	Lime and shale
2815	2900	Lime and shale
2900	3000	Lime and shale
3000	3075	Lime and shale
3075	3135	Lime and shale
3135	3165	Lime and shale
3165	3180	Lime and shale
3180	3225	Lime
3225	3280	Lime
3280	3310	Lime
3310	3355	Lime
3355	3400	Lime
3400	3445	Lime
3445	3475	Lime
3475	3524	Lime
3524	3580	Lime
3580	3620	Lime
3620	3640	Lime
3640		Rotary Total Depth

CASING RECORD

Set 8-5/8" surface casing at 186', cemented with 125 sacks cement.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Jacobs #1 located SW SW SE Section 26-11S 18, Ellis County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.
By: H. R. Jensen

Subscribed and sworn to before me this 20th day of March, 1950.

Martha Kraus
Notary Public

My Commission expires September 12, 1953

PLUGGING
FILE SEC 26 T 11 R 18
BOOK PAGE 143 LINE 24