


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give Information Completely
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 26 Twp. 11s Rge. (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines C W/2 NW SE
Lease Owner American Petrofina Company of Texas
Lease Name Jacobs "B" Well No. 1
Office Address Box 209 - Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed July 1 19 59
Application for plugging filed June 2 19 59
Application for plugging approved June 8 19 59
Plugging commenced June 8 19 59
Plugging completed June 16 19 59



Locate well correctly on above
Section Plat

Reason for abandonment of well or producing formation
Insufficient Production
If a producing well is abandoned, date of last production January 23 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Conglomerate Depth to top 3630 Bottom 3646 P.B. Total Depth of Well 3666 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	1382	8 5/8"	1382	0
		0	3675	5 1/2"	3675	3055.17'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 3600'

Run 4 sacks of cement at 3600'

Pumped 20 sacks of mud at 550'

Pumped 20 sacks of cement at 550'

Pumped 20 sacks of cement at 160'

Run 10 sacks of cement to cap.

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C. E. Shull Casing Pulling Company
Address Box 558 Great Bend, Kansas License No. 8

STATE OF KANSAS COUNTY OF RUSSELL ss.
LEVI B. SHEERMAN District Superintendent - Kansas
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Levi B. Sheerman
Box 209 - Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 59

Notary Public.

My commission expires 10-2-60

PLUGGING
FILE SEC 26 T 11 R 18 W
BOOK PAGE 12 LINE 28

OPERATOR: El Dorado Refining Co.
El Dorado, Kansas

CONTRACTOR: Mast Drilling, Inc.
Russell, Kansas

LEASE: Jacobs "B" #1
C W/2 NW/4 SE/4
Sec. 26-11s-18w
Ellis County, Kansas

COMMENCED: 6-19-55

COMPLETED: 7-1-55

FORMATION	DEPTH
Rock	35
Sand	95
Shale	120
Shale & Shells	495
Sand	680
Sand & Shale	770
Shale	776
Pierite	798
Shale-Lime	1175
Shale-Red Bed	1375
Red rock-Shale	1382
Anhydrite	1427
Red Rock-Shale	1610
Shale	2000
Lime-Shale	2515
Lime	2815
Lime-Shale	2940
Lime	3015
Lime-Shale	3150
Lime	3226
Shale-Lime	3426
Lime	3638
Conglomerate	3651
Simpson	3678
Arbuckle	3680

8 5/8" casing: set at 1382' with
650 sacks cement.

5 1/2" casing: set at 3675' with
100 sacks cement.

Perforations at 3631-36' and
3656-61'.

TOTAL DEPTH 3680

Plugged Back Total Depth: 3666'.

I hereby certify that the above is true and correct to the best of my knowledge.

MAST DRILLING, INC.,

By: James J. Thoman
Secretary

STATE OF KANSAS)
COUNTY OF RUSSELL) SS

Subscribed and sworn to before me this 11th day of July, 1955.

Betty Jean Galyardt
Notary Public

FILED
STATE OF KANSAS
JUN 3 1959
CONSERVATION DIVISION
Wichita, K.

My commission expires 8-9-58.

PLUGGING
FILE SEC 26 T. 11. R. 26W
BOOK PAGE 42 LINE 22

15-051-30679-0000

Brief Plugging Record on
American Petrofina Co. of Texas's
Jacobs "B" Well #1, in
Ellis County, Kansas

Total depth 3680'

5½" casing set at 3675'

Cemented with 100 sacks

8 5/8" casing set at 1382'

Cemented with 650 sacks

Filled hole with sand to 3600'

Run 4 sacks of cement at 3600'

Pumped 20 sacks of mud at 550'

Pumped 20 sacks of cement at 550'

Pumped 20 sacks of cement at 160'

Run 10 sacks of cement to cap

Work started June 8, 1959
Work completed June 16, 1959

C. E. Shull Casing Pulling Company
Box 558
Great Bend, Kansas

License No. 8

