


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Ellis County, Sec. 2 Twp. 11 Rge. 19 (E) W (W)  
Location as "NE/CNWxSWK" or footage from lines SW SW SW  
Lease Owner Trans Era Petroleum, Inc.  
Lease Name O'Brien Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 11/4/53 19  
Application for plugging filed 11/2/53 19  
Application for plugging approved 11/2/53 19  
Plugging commenced 11/3/53 19  
Plugging completed 11/3/53 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3660 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	207	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING RECORD

Filled hole with mud to 200', set bottom plug with 415 sacks of cement. Filled hole with mud to 40', set top plug with 1/2 sack of hulls and 10 sacks of cement.

11-21-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. R. Michaelis*  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1953

*Margie Cooper*  
Notary Public.

My commission expires 1-30-57.

PLUGGING  
FILE SEC 2 T 11 R 19W  
BOOK PAGE 14 LINE 15

Frank E. Peterson, Eng.  
Operator #1

SW SW SW 2-11-19  
Ellis County, Kas.

Total Depth 3661  
Comm. 10/21/53  
Comp. 11/4/53

Chasing

Cement

3 1/8" Hole @ 207'

125 sacks cement

Formation	Depth
Shale	207
Shale-shells	645
Sand	740
Shale	900
Sand	1095
Shale-sand	1150
Red rock-shale	1390
Red bed-shale	1430
Anhydrite	1479
Red bed-shale	1518
Shale-shells	1990
Shale-lime	3328
Lime	3539
Conglomerate	3601
Siliceous	3621
Archean	3628
Lime	3660'

STATE OF KANSAS )  
RUSSELL COUNTY ) ss

I hereby certify that the above information is true and correct to the best of my knowledge.

*Carly Betz*

Subscribed and sworn to before me this 19th day of November, 1953.

*Margie Cooper*  
Notary Public

My commission expires: 1-30-57.

**PLUGGING**  
FILE SEC 2 T 11 R 19  
BOOK PAGE 141 LINE 15

RECEIVED  
STATE OF KANSAS COMMISSION  
NOV 21 1953  
CONCRETE DIVISION  
Wichita, Kansas