

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 35 Twp. 11 Rge. (E) 18 (W)

Location as "NE/CNWxSWx" or footage from lines NW NE SW

Lease Owner Graham-Messman-Rinehart Oil Company

Lease Name Glinther Well No. 1

Office Address 1005 E. Second St., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 9, 19 53

Application for plugging filed April 9, 19 53

Application for plugging approved April 13, 19 53

Plugging commenced April 9, 19 53

Plugging completed April 9, 19 53

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Box 326, Hays, Ks.

Producing formation Depth to top Bottom Total Depth of Well 3715 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	160	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 155'. First plug @ 155'
w/ 3/4 sk. hulls and 15 sx. cement.
Top plug @ 140' w/ 3/4 sk. hulls and
10 sx. cement. Mud to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Oil Company

Address 1005 E. Second St., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. A. Gilliland (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland

1005 E. Second St., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 19 53

Barbara J. Scott Notary Public.

My commission expires December, 1, 1956

24-2675-5 2-52-20M

PLUGGING
FILE SEC 35 T 11 R 18 W
BOOK PAGE 22 LINE 19

ED
COMMISSION
APR 16 1953
SERVATION DIVISION
Wichita, Kansas

GIINTHER #1WELL RECORD

Location: NW NE SW, Sec. 35-11-18W
Ellis County, Kansas

Commenced: March 30, 1953

Operator: G-M-R Oil Company

Completed: March 9, 1953

Contractor: G-M-R Drilling Co.

Production: D & A

Casing Record: 8 5/8" @ 160' w/100 sx,

Elevation: 2130 K.B.

LOG

Sod & Rock	38
Sand	70
Blue Shale	160
Shale Shells	660
Sand	1050
Shale Red Bed	1285
Shale	1392
Anhydrite	1425
Shale	1590
Shale	1979
Fort Riley Lime	2071
Brown Lime	2260
Shale & Lime	2369
Shale & Lime	2540
Lime Shale	2685
Lime & Shale	2802
Lime & Shale	2990
Shale Lime	3115
Shale & Lime	3225
Lime	3265
Lime	3335
Lime	3384
Lime	3420
Lime	3482
Lime	3526
Lime	3565
Lime	3625
Lime	3632
Lime	3641
Lime	3664
Lime	3685
Arbuckle	3715 T.D.

TOPS

3124	-- Topeka (-994)
3352	-- Heebner (-1222)
3371	-- Toronto (-1241)
3395	-- Lansing (-1265)
3650	-- Conglomerate (-1520)
3665	-- Simpson (-1535)
3685	-- Arbuckle (-1555)

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By

J. A. Gilliland


J. A. Gilliland

Subscribed and sworn to before me this
15th day of April, 1953.

Barbara J. Scott

Notary Public

My Commission expires: December 1, 1956



SEARCHED
SERIALIZED
INDEXED
MAY 1953