FORM C

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-135-21880-0000

RECEIVED
SEP 27 1980
PALOMINO PETROLEUM

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 5 Twp. 17S Rge. 23W E/W
Location as "NE/CNW¼SW¼" or footage from lines
C E/2 SW SE
Lease Owner Palomino Petroleum
Lease Name Harkness "K" Well No. #1
Office Address 500 Insurance Building, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole
Date Well completed September 17, 1980 19
Application for plugging filed September 17, 1980 19
Application for plugging approved September 17, 1980 19
Plugging commenced September 17, 1980 19
Plugging completed September 17, 1980 19
Reason for abandonment of well or producing formation
dry hole
If a producing well is abandoned, date of last production
19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4510'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

CASING RECORD

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows:
70 sacks @ 1100', 25 sacks @ 270', hulls and 10 sacks @ 40',
2 sacks in mousehole, 3 sacks in rathole; plugging completed
at 8:00 p.m., September 17, 1980.

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 80.

Loretta Dam
Notary Public

My commission expires 3-28-84

Notary Public.

RECEIVED
SEP 27 1980
PALOMINO
PETROLEUM

15-135-21880-0000

DRILLERS LOG

#1 Harkness "K"

CASING RECORD:
7 jts. new 20#
8-5/8" surface
casing

TOTAL ROTARY
DEPTH: 4510'

COMPANY: Palomino Petroleum

CONTRACTOR: Strata Drilling Company

COMMENCED: September 10, 1980

COMPLETED: September 17, 1980

DESCRIPTION: C E/2 SW SE
Section 5-17S-23W
Ness County, Kansas

ELEVATION: 2458' KB

D & A

FORMATION	FROM	TO
Shale, rock, shale	0	285
Shale, sand, shale	285	1785
Anhydrite	1785	1820
Shale	1820	2475
Lime and shale	2475	4090
Lime	4090	4265
Lime and shale	4265	4510

REMARKS

Ran 274' new 20# 8-5/8" surface casing; set and cemented at 279' with 180 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 9:15 p.m., September 10, 1980.

Ran 2 drill stem tests.

Hole plugged with 50-50 pozmix,6% gel, as follows: 70 sacks at 1100', 25 sacks at 270', hulls and 10 sacks at 40', 3 sacks in rathole, 2 sacks in mousehole. Plugging completed at 8:00 p.m., September 17, 1980.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1980
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp

Charles W. Steincamp

Sworn to and subscribed before me this 25th day of September, 1980.

My appointment expires 3-28-84.

Loneita Barry

Loneita Barry, Notary Public