


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

_____ Ness County, Sec. 7 Twp. 17S Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines C/NW SE
Lease Owner Dunigan Operating Company
Lease Name Gerhardt Well No. 1
Office Address P. O. Box 261, Pampa, Texas 79065
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 25 19 73
Application for plugging filed April 25 19 73
Application for plugging approved April 25 19 73
Plugging commenced April 25 19 73
Plugging completed April 25 19 73
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	372'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole as follows: Plugged at 750' with 70 sacks of common cement, 50-50 pozmix; plugged at 300' with 20 sacks of common cement, 50-50 pozmix; bridge at 40' filled to top with 10 sacks of common cement, 50-50 pozmix. All pozmix had 6% gel in it. Plug down at 6:00 P. M. April 25, 1973.

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1973

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)



Subscribed and sworn to before me this 26th day of April, 19 73.
Elaine H. Taylor
Elaine H. Taylor Notary Public.

DRILLERS LOG

15-135-26737-0000

#1 Gerhardt

CASING RECORD:
366.63' of used 8-5/8"
surface casing.

COMPANY: Dunigan Operating Company
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/NW SE
Section 7-17S-23W
Ness County, Kansas

TOTAL DEPTH:
4550'

COMMENCED: April 17, 1973
COMPLETED: April 25, 1973

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	190	Ran 366.63' of used 8-5/8" surface casing; set and cemented at 372' with 225 sacks of common cement, 2% gel and 3% C. C. Plug down at 10:15 P. M. April 18, 1973.
Shale & Sand Streaks	190	420	
Shale, Red Bed & Sand Streaks	420	1166	
Blaine	1166	1172	
Shale	1172	1300	
Sand	1300	1440	
Sand & Shale	1440	1896	
Shale & Lime	1896	2372	
Shale & Lime	2372	4360	
Lime	4360	4442	
Lime & Shale	4442	4550	

ROTARY TOTAL DEPTH 4550'

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1973
CONSERVATION DIVISION
Wichita, Kansas
D. & A.

Plugged hole as follows: Plugged at 750' with 70 sacks of common cement, 50-50 pozmix; plugged at 300' with 20 sacks of common cement, 50-50 pozmix; bridge at 40' filled to top with 10 sacks of common cement, 50-50 pozmix. All pozmix had 6% gel in it. Plug down at 6:00 P. M. April 25, 1973.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 26th day of April, 1973.
My Commission Expires:
December 14, 1973

Elaine H. Taylor
Elaine H. Taylor, Notary Public