

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,386-0000

LEASE NAME Sargent

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

3300 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR Blackhawk Exploration, Inc.

SEC. 11 TWP. 17S RGE. 23 ~~XXXX~~(W)

ADDRESS 200 E. First, Suite 100, Wichita, KS 67202

COUNTY Ness

PHONE#(316) 265-6431 OPERATORS LICENSE NO. 4480

Date Well Completed 10-04-89

Character of Well D&A

Plugging Commenced 10-04-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-05-89

The plugging proposal was approved on 10-05-89 (date)

by State Plugger, Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	323.80'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circulate heavy mud 15 minutes. 1st plug from 1780' to 1580' w/50 sx. 2nd plug from 850' to 530' w/80 sx. 3rd plug from 340' to 180' w/40 sx. 4th plug from 40' SB to surface w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Blackhawk Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. 10-19-89

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton
(Address) 150 N. Main, Suite 801
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 17th day of October, 19 89

My Commission Expires: May 18, 1993
Sharan J. Branstetter Notary Public

