

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202  
KANSAS CORPORATION COMMISSION

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-239360001  
LEASE NAME Albers  
WELL NUMBER 1

FEB 22 1999  
2-22-99

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2970 Ft. from S Section Line  
330 Ft. from E Section Line  
SEC. 17 TWP. 17 RGE. 23 (E) or (W)

LEASE OPERATOR Knighton Oil Company, Inc.

ADDRESS 221 S. Broadway, Suite 710 Wichita, KS 67202 COUNTY Ness

PHONE# (316) 264-7918 OPERATORS LICENSE NO. 5010

Date Well Completed 12/14/98

Character of Well D & A

Plugging Commenced 2/16/99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/16/99

The plugging proposal was approved on 2/16/99 (date)

by Michael Maier (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4504

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		312	0	8 5/8"	312'	None
Production Casing				5 1/2"	4502'	3392

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged with 150 sacks 60/40 Pozmix, 6% gel as follows: sand bottom 50' above perforations, 4 sacks cement-dump bailer, 50 sacks @ 1750', 50 sacks @ 850', 40 sacks @ 320' and 10 sacks @ 40'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mike Kelso Oil, Inc. License No. 31528

Address P.O. Box 467 Chase, Kansas 67524-0467

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

David D. Montague (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David D. Montague


(Address) 221 S. Broadway Wichita, KS

SUBSCRIBED AND SWORN TO before me this 22 day of February, 19 99

Carol A. Brane

Notary Public

My Commission Expires: 3-17-02



Form CP-4  
Issued 05-83