

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Ness County, Sec. 18 Twp. 7S Rge. 23W 6E (W)

Location as "NE/CNW/SW" or footage from lines C SW NE

Lease Owner TILCO etal

Lease Name Herrick Well No. 1

Office Address Box 486, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-14-68 19

Application for plugging filed 4-14-68 19

Application for plugging approved 4-14-68 19

Plugging commenced 4-14-68 19

Plugging completed 4-14-68 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4539 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 319'   | none       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud, spotted 70 sks. 50/50 Posmix 6% gel @ 900', spotted 20 sks. 50/50 Posmix @ 300', bridged @ 40' with 1/2 sk. hulls

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite

(employee or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

Box 486, Great Bend, Kansas 67530 (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of April, 1968

My commission expires April 1, 1971

Notary Public.

DRILLER'S LOG

COMPANY: TILCO etal  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: HERRICK #1  
 LOCATION: C SW NE SECTION 18-17S-23W  
 NESS COUNTY, KANSAS  
 COMMENCED: 4-6-68  
 COMPLETED: 4-14-68

|      |             |                            |
|------|-------------|----------------------------|
| 0    | 130         | Surface soil, rock, gravel |
| 130  | 190         | Gravel, sand               |
| 190  | 580         | Shale                      |
| 580  | 710         | Sand                       |
| 710  | 1195        | Redbed, Shale              |
| 1195 | 1793        | Redbed, sand               |
| 1793 | 1828        | Anhydrite                  |
| 1828 | 2430        | Shale, Shell               |
| 2430 | 2500        | Shale, Lime                |
| 2500 | 2675        | Lime                       |
| 2675 | 2968        | Lime, Shale                |
| 2968 | 3420        | Shale, Lime                |
| 3420 | 3930        | Lime, Shale                |
| 3930 | 4500        | Lime                       |
| 4500 | 4539        | Lime, Chert                |
|      | <u>4539</u> | <u>RTD - D&amp;A</u>       |

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 17 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

8 5/8" new 20# surface casing set @ 319' cemented with 185 sacks  
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is  
 a true and correct copy of the log of the Herrick #1 Well, loca-  
 ted C SW NE of Section 18, Township 17 South, Range 23 West, of  
 Ness County, Kansas, as reflected by the records of Leben Drilling,  
 Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in  
 and for Barton County, Kansas, this 16th day of April, 1968.

Ulanda Nichols  
 Ulanda Nichols

My Commission Expires:  
 April 1, 1971