

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County. Sec. 19 Twp. 17S Rge. 23W(E) (W)
Location as "NE/CNW&SW" or footage from lines. C NE SE
Lease Owner Alpine Drilling Co., Inc.
Lease Name Anspaugh Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed December 20, 1971 19
Application for plugging filed December 20, 1971 (by phone) 19
Application for plugging approved December 20, 1971 (by phone) 19
Plugging commenced December 20, 1971 19
Plugging completed December 20, 1971 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes


Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4468 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8-inch	288 ft.	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug and 70 sacks cement at 700 feet. 20 sacks cement at 270 feet. Plug and 1/2 sack hulls at 40 feet. Filled up with 10 sacks cement.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jon T. Williams, Jr. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jon T. Williams, Jr. (Address)

Subscribed and sworn to before me this 20th day of December, 1971
Evelyn Wanko Notary Public.

My commission expires December 10, 1972



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

ANSPAUGH #1
 C NE SE, Sec. 19-17S-23W
 Ness County, Kansas

Commenced: December 6, 1971
 Completed: December 20, 1971

OPERATOR: ALPINE DRILLING CO. INC.

15-135-70523-0000

Depth From	To	Formation	Remarks
0	40	Surface clay-shale	Ran 6 jts of used 28# 8 5/8" csg.
40	1150	Shale	set @ 293' w/175 sks 60-40 Posmix
1150	1400	Sand	3% CC. Centralizer 5' below collar
1400	1705	Shale and lime	on shoe jt.
1705	1740	Anhydrite	P.D. 12 AM 12/7/71
1740	2480	Shale and lime	Cement Circ. Job by Halco
2480	3860	Lime and shale	
3860	4365	Lime	
4365	4426	Lime and chert	
4426	4468	Lime	
4468	TD		Dry and Abandoned


I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE SE, Section 19-17S-23W, Ness County, Kansas, to the best of my knowledge and belief.

James S. Sutton, II
 James S. Sutton, II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 23rd day of December, 1971, personally appeared James S. Sutton, II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.



Marjorie Hall
 Marjorie Hall, Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 23 1971
 CONSERVATION DIVISION
 Wichita, Kansas