

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company

Complete Address: 617 Union Center Wichita, Kansas

Lease Name Jacobs-Peavy Well No. 1

Location App/ SE NW SE Sec. 26 Twp. 11 Rge. 18 (E) (W) X

County Ellis Total Depth 3710'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: J. O. Farmer Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 12N Day 31 Month 12 Year 1968

The Above well was plugged as follows:

RTD 3710' 8 5/8 csg set at 183' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt.
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 30 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *Red A. Mansury*
Well Plugging Supervisor

INVOICED

DATE 1-2-69

INV. NO. 9135-W