

FILED
STATE OF KANSAS

JUN 24 1959

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 42-28 County: Ellis

Location: CW $\frac{1}{2}$ NW SE Sec. 26 Twp. 11 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3680

I have this date completed supervision of plugging of:

Lease Name: Jacobs Well No. B-1

Operator's Full Name: American Petrofina Co

Complete Address: Box 209 Russell, Kans

Plugging Contractor: C. E. Shull & Sun Cementing Co

Address: Great Bend, Kans License No. 8

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 1PM Day 15 Month 6 Year 59

The above well was plugged as follows:

8 5/8" at 1382' circulated with 650 sax cement - 5 1/2" 3675' with 100 sax cement- PB to 3666' - perforations 3631'

Filled with sand to 3600', set 4 sax cement with dump bailer, pulled 3055', 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" (21 sax Gel), displaced 20 sax cement through 5 1/2" at 550', mud to 160', displaced 20 sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed:
Conservation Division Agent

Reviewed:
Field Supervisor

Remarks:

Note: Change file no. on all other forms on this lease to 58-26

PLUG - 159
FILE SEC 26T. 11 18N
BOOK PAGE 52 L. 26