

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
MAY 11 1960
CONSERVATION DIVISION
WICHITA, KANSAS

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: SW NE SW Sec. 2 Twp. 11 Rge. 19 (E) (W)

Name of Field: _____ Total Depth: 3651

I have this date completed supervision of plugging of:

Lease Name: Herman Well No. 1

Operator's Full Name: Leben Drg Co

Complete Address: 905 Central Bldg Wichita, Kans

Plugging Contractor: Southwest Casing Pulling Co

Address: Great Bend, Kans License No. 399

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 2 Month 5 Year 60

The above well was plugged as follows:

8 5/8" 221' circulated with cement - 5 1/2" 3650' with 100 sax cement behind.

P.B. to 3097' - perforated 3079.

Filled with sand to 3060', set 4 sax cement with dump bailer, pulled 2520' 5 1/2" to 500', circulated hole with heavy mud (35 sax Gel), displaced 20 sax cement through 5 1/2" at 500', mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE: 5/16/60
INV NO. 1352-W