

R

Form CP-3
Rev 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 07 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051 - 21,283 - 0000 (of this well)

Operator's Full Name R. P. Nixon Operations

Complete Address Box 589, Russell, Kansas

Lease Name Billinger Well No. 1

Location SW SW NE Sec. 2 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3645'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Revin Drlg.

Address Russell, Kansas License No.

Operation Completed: Hour 2:15 P Day 4 Month 3 Year 1977

The above well was plugged as follows:

RTD 3645' 8 5/8 csg set 216' cwc 150 sx. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Reo Massey
Well Plugging Supervisor

DATE 3-7-77

INV. NO. 4746-W