

12-9-59

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1959
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: CS $\frac{1}{2}$ SW SW Sec. 35 Twp. 11 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3588

I have this date completed supervision of plugging of:

Lease Name: Gunther Well No. 1

Operator's Full Name: Jay Bergman Oil Co

Complete Address: 425 Union Center Wichita, Kans

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 342

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 30 Month 11 Year 59

The above well was plugged as follows:

8 5/8" 1108' circulated with cement - 5 1/2" 3581' with 100 sax cement.
set 7 sax cement on bottom with dump bailer, pulled 2400' 5 1/2" to 550',
circulated hole with heavy mud (Gel) through 5 1/2" at 550', displaced
20 sax cement through 5 1/2" at 550', heavy mud to 200', displaced 20 sax
cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sax cement
to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 1/14/60
INV. NO. 661-W