

DISTRICT CONSERVATION AGENT'S REPORT

*[Handwritten mark]*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW SE SW

SEC. 33 TWP. 11 RGE. 18

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Johnson

Operator Sunray Mid Continent Oil Co. Address Box 788 Great Bend, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3715 Feet.

Plugging Contractor Steckel Drg Co & Halliburton Co

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 261' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at  
600', displaced 20 sax cement through drill pipe, heavy mud to 240',  
set cementing plug and displaced 20 sax cement through drill pipe, heavy  
mud to 40', set cementing plug, hulls and 10 sax cement to bottom cellar.

Cementing by Halliburton Co.

Gilbert Leiker

By *[Signature]*

District Conservation Agent

Date 12-16-57

PLUGGING  
SEC 33 T11 R 18W  
BOOK PAGE 70 LINE 43

STATE OF KANSAS  
CONSERVATION DIVISION

DEC 24 1957

CONSERVATION DIVISION  
Wichita, Kansas