

**KANSAS  
STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

OCT 1 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Hummon Oil, Inc.

Complete Address: 821 Union Nat'l Bldg., Wichita, Kansas

Lease Name Johnson Well No. 1

Location C SW SW NW Sec. 33 Twp. 34 Rge. (E) (W) 18

County Ellis Total Depth 3667'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XI

Other well as hereafter indicated:     

Plugging Contractor: H-30 Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 8:30A Day 29 Month 9 Year 1969

The Above well was plugged as follows:

RTD 3667' 8 5/8 csg set at 247' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 240' set cementing pluf and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 10/1/69  
INV. NO. 569-W

Signed: Leo J. Massey  
Well Plugging Supervisor