

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mendo Oil Corporation

Complete Address 5810 N. Eastern Oklahoma City, Oklahoma 73111

Lease Name Johnson ~~SP~~ Well No. A-1

Location NE NW SW Sec. 33 Twp. 11 Rge. (E) (W) 18

County Ellis Total Depth 3699'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Leben Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30A Day 26 Month 9 Year 1969

The above well was plugged as follows:

RTD 2699' 8 5/8 csg set at 222' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/29/69

INV. NO. 544-W

Signed: Leo A. Messing
Well Plugging Supervisor