

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-SE-SE

SEC. 4 TWP. 11 RGE. 19W

Dry Hole *** Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Forgue

Operator C - G Drilling Company. Address 107 Rule Bldg.
Wichita, Kansas.

Field _____ County Ellis

Total Depth 3677' Feet.

(Describe briefly the manner in which the well was plugged)

Plugging Contractor. - C-G Drilling Company.

Plugging Contractor's License. No. - _____

Address. - 107 Rule Bldg. Wichita, Kansas.

Surface pipe - 8 5/8" set @ 185' c.w.c. 150 sx.

Filled hole with heavy mud to 180' from top. 1/2 sx. hulls, H.O.W.C.O.

plug and 15 sx. cem. through drill pipe. Mud to 40' from top. 1/2 sx.

hulls, H.O.W.C.O. plug and 10 sx. cem. to base of cellar.

08-31-56

Wilton G. Gandy
District Conservation Agent

Date 8-29-56

PLUGGING
FILE SEC. 4 T. 11 R. 19W
BOOK PAGE 94 LINE 44