

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas

Lease Name Pulec "B" Well No. 1

Location C N/2 NW SW Sec. 4 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3150'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 9:45 P Day 13 Month 5 Year 1973

The above well was plugged as follows:

RTD 3150' 8 5/8 csg set at 207' cwc. Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 685' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 5/16/73

INV. NO. 7363-W