

15-135-20458-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*4*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 2 1971  
CONSERVATION DIVISION  
Wichita, Kansas

08-02-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Martin Explorations

Complete Address 527 Union Center Wichita, Kansas

Lease Name Horchem Well No. 2

Location NW SW NW Sec. 6 Twp. 18 Rge. (E) (W) 23

County Ness Total Depth 4370'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Dreiling Oil

Address Victoria, Kansas License No.       

Operation Completed: Hour 5 A Day 27 Month 7 Year 1971

The above well was plugged as follows:

RTD 4370' 8 5/8 csg set at 322' cwc 200 sk. Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Ken A. Murray*  
Well Plugging Supervisor

DATE 8-4-71

INV NO. 4088-W