

15-135-20677-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1972
09-29-1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Martin Oil Company

Complete Address 527 Union Center Wichita, Kansas

Lease Name Horchem Well No. 3

Location 150' NW of C NE NW Sec. 6 Twp. 18 Rge. (E) (W) 23

County Ness Total Depth 4412'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 11:50 P Day 26 Month 9 Year 1972

The above well was plugged as follows:

RTD 4412' 8 5/8 csg set at 319' cwc 175 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing
Well Plugging Supervisor

RECEIVED
9/29/72
INV. NO. 6385-4