

15-135-20485-00-00

Form CP-3
Rev. 6-4-68

KANSAS

4 STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1971
CONSERVATION DIVISION
Wichita, Kansas

09-28-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company

Complete Address 415 Page Court 220 W Douglas Wichita, Kansas

Lease Name Huenergardt "A" Well No. 1

Location NE SW Sec. 7 Twp. 18 Rge. (E) (W) 23

County Ness Total Depth 4420'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil

Address Wichita, Kansas License No.

Operation Completed: Hour 9 P Day 26 Month 9 Year 1971

The above well was plugged as follows:

RTD 4420' 8 5/8 csg set at 364' cwc 180 sk. Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 330' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 9-29-71

INV. NO. 4392-40