

15-05102324-0000

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED

SEP 26 2001

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 1947
LEASE NAME Vine
WELL NUMBER #1
330 ft. from ^NS Section Line
2310 ft. from ^WE Section Line
SEC. 27 TWP. 11 RGE. 19 (E) or (W)
COUNTY Ellis

LEASE OPERATOR KCC WICHITA
Mai Oil Operations, Inc.
ADDRESS PO Box 33, Russell, KS 67665
PHONE # (785) 483-2169 OPERATORS LICENSE NO. 5259

Date Well Completed _____
Plugging Commenced 8/23/01
Plugging Completed 9-17-2001

Character of well oil
(Oil, Gas, D&A, SWD, input, Water Supply Well)
The plugging proposal was approved on 8/23/01 (date)
by Herb Deines (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3646
Show depth and thickness of all water, oil and gas formations
OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1419	none
				5 1/2	3633	1800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Sand at 3281, baled 5 sks cem. Shot pipe at 2649, parted at 1800, pulled to 1510. Pump 15 sks cem. down 13 5/8, pump 105 sks cem. with 3 sks hulls down 5 1/2 at 1510. Pulled to 800, pump 50 sks cem. Pulled to 200', pump 60sks cem. Pull rest of pipe . CEMENT FELL BACK TO 800'. ALLIED FILL 8 5/8" WITH 200 SKS 60-40POZ 6% GEL.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mai Oil Operations, Inc.
STATE OF KANSAS COUNTY OF ELLIS SS.

ALLEN BANGERT (Employee of Operator) or (Operator) of
above - described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above - described well as filled that
the same are true and correct, so help me God.

(Signature) Allen Bangert
(Address) P.O. BOX 33, RUSSELL, KS. 67665

SUBSCRIBED AND SWORN TO before me 25th day of September, 2001
Verna May Hutchings
Notary Public

My commission Expires: April 10, 2005

VERNA MAY HUTCHINGS
State of Kansas
Appt. Exp. 4-10-2005

Form CP-4
Revised 05-88

OK