

15051-21206-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 21 Twp. 11 Rge. 19 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE NE SE

Lease Owner Spud Partnership
Lease Name Berland Well No. 1
Office Address c/o Wm. Bartlett, Box 316, 116 Washington,
Monte Vista, Colo.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed August 9 19 76
Application for plugging filed August 9 19 76
Application for plugging approved August 9 19 76
Plugging commenced August 9 19 76
Plugging completed August 9 19 76

Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3518
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of heavy mud to 550' & 50 sacks 50/50 PozMix, 2% Gel, thru drill pipe
Mud to 240' w/25 sacks 50/50 Pozmix, 2% Gel, thru drill pipe
Mud to 40' w/1/2 sack hulls plug and 10 sacks cement.
2 sacks cement in rat hole.

RECEIVED
AUG 11 1976
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.
Larry Curtis (employee of owner) or (owner)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 823, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 76

Alvin M. Hague
Notary Public.

My commission expires April 11, 1978

DRILLERS' WELL LOG

DATE COMMENCED: August 2, 1976
 DATE COMPLETED: August 9, 1976

SPUD PARTNER
 BERLAND # 1
 C SE NE SE
 Sec 21-T11-R19W
 Ellis County, Kansas

ELEVATION: 1971 M.D.

0 - 324'	Shale, Streaks Sand
324 - 722'	Clay, Shale
722 - 945'	Shale, Sand
945 - 1287'	Red Bed
1287 - 1325'	Anhydrite
1325 - 1883'	Shale
1883 - 2945'	Shale and Lime
2945 - 3168'	Lime
3168 - 3172'	Shale
3172 - 3207'	Lime
3207 - 3512'	Lime and Shale
3512 - 3518'	Dolomite
3518'	RTD

FORMATION TOPS

Anhydrite	1287
Topeka	2945
Heebner	3168
Lansing	3207
Arbuckle	3512
RTD	3518

SURFACE PIPE:

Set used 8 5/8", 28# pipe
 @ 324' w/175 sacks cement,
 2% Gel.

AFFIDAVIT

STATE OF KANSAS }
 COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 9th day of August, 1976.

Larry Curtis

Henry M. [Signature]
 Notary Public

My Commission Expires: April 11, 1978