

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-19155-0000

API NUMBER 11-10-64

LEASE NAME Gaylord Solomon

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 21 TWP. 11S RGE. 19 (E) or (W)

COUNTY Ellis

Date Well Completed 11-10-64

Plugging Commenced 5-12-88

Plugging Completed 5-12-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Don E. Pratt Oil Operations

ADDRESS 1011 Fort St. - Hays, KS 67601

PHONE# (913) 625-3446 OPERATORS' LICENSE NO. 6114

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3488' Bottom 3494' T.D. 3494'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	181'	None
				5 1/2	3489'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

200 sacks 65/35 Pox 10% gel & additives - D.V @ 1256' with 309 sacks cement
circulated to surface - Anhydrite 1246-92'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License None

Address 1100 E 8th Street

STATE OF Kansas COUNTY OF Ellis, ss.

Don E. Pratt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Don E. Pratt

(Address) P.O. Box 370 - Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 88

My Commission Expires: _____



Notary Public Helen Ubert

15-051-19155-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas




Company- DON E PRATT OIL OPERATIONS
Farm- Soloman No. 1

SEC. 21 T. 11 R. 19W
NW NW NE

Total Depth. 3494'
Comm. 11-2-66 Comp. 11-10-64
Shot or Treated.
Contractor. LEDEN DRILLING
Issued. 2-13-65

County Ellis
KANSAS



CASING:

8 5/8" 181' cem w/ 150 sx
5 1/2" 3494'

Elevation. 1954' KB

Production. 25 BOPD-NW

Figures Indicate Bottom of Formations.

sand	80
sand, clay, shale	181
shale	710
Dakota sand	1010
red shale, shells	1245
anhydrite	1292
shale, shells	1585
shale, lime	2090
lime, shale	2275
shale, lime	3045
lime, shale	3128
lime	3415
lime, chert	3473
conglomerate	3488
Arbuckle	3494 RTD
Total Depth	

TOPS:SMP	
Anhydrite	1246-92
Topeka	2922
Heebner	3141
Toronto	3161
Lansing	3181
Base Kansas City	3411
Arbuckle	3488