

Kansas Corporation Comm.  
Wichita State Office Bldg.  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 5051-24906 0000

LEASE NAME Sessin

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1  
1270 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 21 TWP. 11S RGE. 19 (E or W)

COUNTY Ellis

LEASE OPERATOR Castle Resources, Inc.

ADDRESS 1200 East 27th #C Hays, Kansas 67601-2120

PHONE# (913) 625-5155 OPERATORS LICENSE NO. 9860

Character of Well D&A

(Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 10/26/95

Plugging Commenced 2:00PM 10/26/95

Plugging Completed 4:00PM 10/26/95

The plugging proposal was approved on 10/26/95 (date)

by Ed Schumacher (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	214	8 5/8	214.33	None

STATE CORPORATION COMMISSION  
RECEIVED  
NOV 1 1995

Describe in detail the manner in which the well was plugged, indicating where the mud or fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

- 1st Plug @ 1290' w/20sks Circulated 1st Plug 15 Minutes w/ 54 VIS Mud
- 2nd Plug @ 605' w/100sks Displaced Plugs w/ mud
- 3rd Plug @ 265' w/ 40sks 195 sks 60/40 Poz 6% Gel w/ 1/2 FS/sk By Allied Cementing
- 4th Plug @ 40' w/ 10sks (10sks In Mouse Hole) (15sks In Rat Hole)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources, Inc.

STATE OF Kansas COUNTY OF ELLIS, ss.

Castle Resources, Inc. (Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed: the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1200 E. 27th Suite C Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1995.

Nancy Taggart  
Notary Public



Expires: 7-2-99