

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-135-23,420⁰⁰ (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Downing-Nelson Oil OPERATOR'S LICENSE NO. 04373 ^{5/90}

ADDRESS POB 372 Hays, KS. 67601 PHONE # (913) 628-3449

LEASE (FARM) GRM WELL NO. 1 WELL LOCATION N/2-S/2 SW COUNTY NESS

SEC. 7 TWP. 18 RGE. 23 (E) or (W) TOTAL DEPTH 4390 PLUG BACK TO CIBP@ 4156

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 205' CEMENTED WITH 140 SACKS

CASING SIZE 5 1/2" SET AT 4392 CEMENTED WITH 180 SACKS

PERFORATED AT 4368-71; 4362-58; 4342-50; CIBP@ 4156; REPER@ 411-21

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING SAND FROM BRIDGE PLUG TO 50' OVER PERES, 5 SKS cement with bailer, free point & shoot off casing, pull casing; plug through 8 5/8" w/ 200 SKS cement, starting with 400# hulls, 10 SKS gel, 75 SKS cement, 10 SKS gel, 1 SK hulls, 8 5/8" plug, 125 sacks cement
(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? NO
(If not explain.) ACO is being processed as is geological report. Will send within 10 days.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3-10-90 @ 8:00 Am

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

RON NELSON PHONE # (913) 628-3449

ADDRESS 215 E. 5th Hays, KS. 67601

PLUGGING CONTRACTOR Plams Well Service Inc. LICENSE NO. 4072 ^{11/90}

ADDRESS POB 346 NESS CITY, KS 67560 PHONE # (913) 798-3995

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

CONSERVATION DIVISION
Wichita, Kansas
03-16-1990

SIGNED: Ron Nelson
(Operator or Agent)

DATE: 3-14-90

①