



15-135-20904-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

NOV 25 1974

CONSERVATION DIVISION  
Wichita, Kansas

11-25-1974

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Cain of Strata Plg. has this

date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Wolland, Inc.

Complete Address: Box 519, Great Bend, Ks.

Lease Name: Finnup Well No. 1

Location: C NE SE Sec. 17 Twp. 18 Rge. (E)(W) 25

County: Ness Total Depth 4478' Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Cain was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 650' thru drill pipe.

Heavy mud to 240' & set 20 sk cmt plug thru drill pipe. Heavy mud to 40'

set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey  
Conservation Division Agent