



15-135-20998-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1975
02-24-1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walker of DNB Drlg. has this

date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: Suite 800, 300 W. Douglas, Wichita, Ks.

Lease Name: Whipple Well No. 1

Location: C SE NW Sec. 19 Twp. 18 Rge. (E)(W) 25

County: Ness Total Depth 4492' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Walker was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 720' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud

to 40' set 1/2 sk hulls, cementing plug & 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey
Conservation Division Agent