

State of Kansas



15-135-21021-00-00

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
ST. J. ...JUL 2 1975  
07-02-1975J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dreiling of Gabbert-Jones Drlg. has this  
date requested permission to plug the following described well:Mr. Dreiling guarantees payment of the plugging fee.Operator's full Name: O. A. SuttonComplete Address: 800 Sutton Place, Wichita, KansasLease Name: Hawkinson Well No. 1Location: 150°E of C SE NW Sec. 34 Twp. 18 Rge. (E)(W) 23County: Ness Total Depth 4440' Oil Well     Gas Well      Input Well      SWD Well      D & A XX Lost Hole     Mr. Dreiling was instructed to plug the well as follows:RTD 4440' 8 5/8 csg set 508' cwc 300 sk. Plg. Mat. 50-50 poz 2% gel.Gunned pits, circulate heavy mud, set 50 sk cmt plug at 550' thru drillpipe. Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy mudto 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

*Geo F. Messing*