


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 35 Twp. 11 Rge. 18 E/W
Location as "NE/CNW/SW" or footage from lines
App. S/2/SE/SE

Lease Owner Petroleum, Inc.
Lease Name Giinther "B" Well No. 1
Office Address Box 1447, Great Bend, KS 67530
Character of Well (Completed as Oil, Gas or Dry Hole) Oil



Locate well correctly on above Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8/16/78 _____ 19____
Plugging completed 8/30/78 _____ 19____
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3540'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	215'	None
				4 1/2	3539'	2757.90'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3220 and four (4) sacks cement
Shot pipe at 3000' and 2800'
Spotted oil behind casing
Pulled 86 joints of 4 1/2" casing
Squeezed well with two sacks hulls, 26 sacks gel, 120 sacks 50/50 pozmix with 6% added gell

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
James W. Rockhold Bx 698 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1978

My commission expires

CATHY L. COLE
Barton County, Kansas
My Appt. Exp. June 14, 1982

Cathy L. Cole
Notary Public.

WELL LOG

COMPANY Petroleum, Inc.

SEC. 35 T. 11S R. 18W

FARM Giinther

NO. B-1

LOC. S/2 SE SE


TOTAL DEPTH 3540'

COUNTY Ellis

COMM. 8-7-66

COMP. 8-17-66

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 215' w/175 sx

4 1/2" @ 3539' w/175 sx

ELEVATION 1986' DF

PRODUCTION KANSAS CITY

FIGURES INDICATE BOTTOM OF FORMATIONS

- 30' Rock and Clay
- 60' Chat and Sand
- 480' Shale
- 815' Sand
- 1870' Shale
- 1885' Shale and Lime
- 2710' Lime and Shale
- 2875' Shale and Lime
- 3260' Lime and Shale
- 3315' Lime
- 3325' Lime and Shale
- 3395' Lime
- 3450' Lime and Shale
- 3475' Lime
- 3520' Lime and Shale
- 3540' Lime
- 3540' RTD

RECEIVED
STATE CORPORATION COMMISSION

SEP 08 1978

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }

County of Barton }

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Giinther B-1 well.

Sam N. Stephens

Subscribed and sworn to before me this 20th day of September 19 66

My Commission Expires: November 5, 1969

Richard Boy
NOTARY PUBLIC