


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ellis County, Sec. 23 Twp. 11S Rge. 18 (E) 18 (W)  
Location as "NE/CNW4SW4" or footage from lines C NE SE SW  
Lease Owner Sunray Mid-Continent Oil Company  
Lease Name Wm. Johnson Well No. 2  
Office Address Box 788, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 15 19 57  
Application for plugging filed December 17 19 57  
Application for plugging approved December 19 19 57  
Plugging commenced December 15 19 57  
Plugging completed December 15 19 57  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Lewis Brock  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3715 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	260	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy drilling mud to 600'. Set Halliburton plug with 20 sacks cement.  
Filled hole with heavy drilling mud to 240'. Set wooden plug with 20 sacks cement.  
Filled hole with heavy drilling mud to 40', set wooden plug and cement to surface.  
Plugging completed.

Well log attached.

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 23 1958  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
N. E. Montgomery (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery  
Box 788, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of January, 19 58

[Signature]  
Notary Public.

My commission expires December 24, 1960

PLUGGED  
33 11 1860  
70 43

Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
December 19, 1957

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: December 4, 1957  
Drilling Completed: December 15, 1957

William Johnson #2 W/2  
Sec. 33-118-18W, Ellis  
County, Kansas.

DRILLERS LOG

Depth figures indicate base of formation:

Surface	0
Surface Clay & Sand	150
Shale	261
Shale & Shells	610
Sand & Shale	1160
Red Bed Shale & Shells	1415
Anhydrite	1455
Red Bed, Shale & Shells	1715
Shale & Shells	1925
Shale & Lime	2190
Lime & Shale	2440
Shale & Lime	2705
Lime & Shale	2820
Lime	2925
Lime & Shale	3265
Lime	3715 TD

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 23 1958  
CONSERVATION DIVISION  
Wichita, Kansas

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's William Johnson #2 W/2 Section 33-118-18W, Ellis County, Kansas.

*Frank E. Stickle*  
Frank E. Stickle

*Lillian T. Bonham*  
Notary Public

February 13, 1960  
My Commission Expires

