

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Location as "NE/CNW/SE/SW" or footage from lines Ellis County, Sec. 33 Twp. 11S Rge. 18W (Section 18)  
 Lease Owner Sunray Mid-Continent Oil Company  
 Lease Name W. Johnson Well No. 1  
 Office Address Box 195, Great Bend, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed September 10 19 55  
 Application for plugging filed September 10 19 55  
 Application for plugging approved September 13 19 55  
 Plugging commenced September 10 19 55  
 Plugging completed September 10 19 55  
 Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3661 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug and abandon with 10# mud from TD to 300'; 25 sack cement from 300' to 220', 10# mud from 220' to 40', and 10 sacks cement from 40' to surface.

Well log attached.

9-21-55

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company  
 Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.  
Norman E. Montgomery (employee of owner) or (conservation division) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman E. Montgomery  
Box 195, Great Bend, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 55

My commission expires December 24, 1956

Stickle Notary Public.

**PLUGGING**  
 FILE SEC 33 T 11 R 18 W  
 BOOK PAGE 149 LINE 25

Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
September 13, 1955

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: August 26, 1955  
Drilling Completed: September 10, 1955

William Johnson #1 W/2  
Sec. 33-11S-18W, Ellis  
County, Kansas.

DRILLERS LOG

Shale & Shells	0-915
Shale	915-1030
Chalky Sandy Lime & Shale	1030-1080
Red Bed & Shale	1080-1160
Red Bed	1160-1381
Anhydrite	1381-1415
Red Bed	1415-1500
Shale & Shells	1500-2145
Shale, Shells & Lime	2145-2265
Lime & Shale	2265-2400
Shale, Lime & Sand	2400-2550
Lime & Shale	2550-2770
Shale & Lime	2770-3035
Lime & Shale	3035-3380
Lime	3380-3428
Lime & Shale	3428-3465
Lime	3465-3519
Lime Hard	3519-3530
Lime	3530-3649
Arbuckle	3649-3661 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of William Johnson #1 W/2 Section 33-11S-18W, Ellis County, Kansas.

William T. Bonham  
Notary Public

February 13, 1956  
My Commission Expires

Frank E. Stickle  
Frank E. Stickle

**PLUGGING**  
FILE SEC-33 T11 R2W  
BOOK PAGE 149 LINE 25