

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 33 Twp. 11 Rge. 18 ~~XXX~~ (W)

Location as "NE/CNW/SW" or footage from lines. C N/2 NE NW

Lease Owner Crescent Oil & Gas Corp.

Lease Name Johnson Well No. 1

Office Address P. O. Box 2460, Dallas, Texas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 10-8 1963

Application for plugging filed 10-8 1963

Application for plugging approved 10-8 1963

Plugging commenced 10-8 1963

Plugging completed 10-8 1963

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3648 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	179	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 550' w/20 sx. cement

Middle plug @ 180' w/20 sx. cement

Top plug @ 40' w/10 sx. cement

STATE CORPORATION COMMISSION

OCT 15 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Jennitti Drilling Co.

Address 706 Union Nat'l. Bldg., Wichita

STATE OF Kansas, COUNTY OF Sedgwick, ss.

K. T. Woodman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman

706 Union Nat'l. Bldg., Wichita (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1963

Frances H. Solomon

My commission expires Oct. 10, 1967

Notary Public.

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Crescent Oil & Gas Corp.

SEC. 33 T. 11 R. 18W
LOC. ~~XXX~~ C N/2 NE NW

FARM Johnson NO. 1

COUNTY Ellis

TOTAL DEPTH 3648'


COMM. 9-27-63

COMP. 10-8-63

SHOT OR TREATED

CONTRACTOR Woodman & Iannitti Drilling Co.

ISSUED



CASING

20 10
15 5/8" @ 179 w/130 sx cement
12 6
13 5

ELEVATION 2077RB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	179	Post Rock & Clay
	600	Shale
	845	Sand & Shale
	1040	Sand
	1375	Red Bed & Shale
	1411	Anhydrite
	1635	Shale & Shells
	1939	Shale & Lime & Shells
	2080	Lime
	2255	Lime & Shale
	2585	Lime
	2700	Lime & Shale
	2915	Lime
	3050	Lime & Shale
	3208	Lime
	3288	Lime & Shale
	3385	Lime
	3455	Lime & Shale
	3540	Lime
	3585	Lime & Shale
	3615	Lime
	3648	Arbuckle

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1963
CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the Driller's Log to the best of my knowledge & belief.

WOODMAN & IANNITTI DRILLING CO.

By: K. T. Woodman
K. T. Woodman