


WELL PLUGGING RECORD

Give All Information Completely
The Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 4 Twp. 11S Rgc. 19W (E) (W)

Location as "NE/CNW&SW&" or footage from lines NW NW SE
Lease Owner Whitestone Petroleum Corporation
Lease Name ROSS Well No. 1
Office Address 900 Vaughn Bldg. - Dallas, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 15 19 63
Application for plugging filed December 16 19 63
Application for plugging approved December 16 19 63
Plugging commenced December 16 19 63
Plugging completed December 16 19 63
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3707⁹ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	221 ⁹	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug @ 540⁹ with 20 sacks cement through drill pipe.
Set second plug @ 180⁹ with 20 sacks cement through drill pipe.
Set third plug @ Bridge @ 40⁹ with 10 sacks. Cement @ bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1963

CONSERVATION DIVISION
Wichita, Kans.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center Building - Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I. C. Robert Buford (employee of ~~owner of well~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. C. Robert Buford
617 Union Center Bldg. - Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 19 63

My commission expires June 14, 1964
May Lane Blaine Notary Public.



WELL LOG

15-051-03788-0000

COMPANY **Whitestone Petroleum Corporation**

SEC. **4** T. **11S** R. **19W**

FARM **ROSS** NO. **One**

LOC. **NW NW SE**

RIG. NO. **Eleven**

TOTAL DEPTH **3707'**

COUNTRY **Ellis**
KANSAS

COMM. **12/6/63**

COMP. **12/16/63**

SHOT OR TREATED **No**

CONTRACTOR **Murfin Drilling Company**

ISSUED

CASING

20	10
15	8 5/8" 221' with 175 sacks cement
12	6
13	5

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 50' Surface Clay and Rock
- 223' Shale
- 676' Shale and Clay
- 930' Shale
- 1130' Sand
- 1448' Red Bed
- 1480' Anhydrite
- 1865' Shale
- 2125' Shale, Shells
- 2275' Shale - Lime
- 2840' Lime and Shale
- 2940' Shale and Lime
- 3105' Lime
- 3255' Lime and Shale
- 3657' Lime
- 3707' Arbuckle
- 3707' Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1963

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
County of Sedgwick ss:

I, C. Robert Buford of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the ROSS #1 well.

C. Robert Buford

Subscribed and sworn to before me this 19th day of December 1963

My Commission Expires: June 14, 1964

May Paul Blum
NOTARY PUBLIC